

UHPC Premix and Constituents

Premix

- cement, silica sand, quartz flour and supplementary cementitious material
- largest "aggregate" grain of sand < 1 mm in dia.
- Admixture
- Water
 - w/c ratio range of 0.20
- Fibers
 - Steel (structural)
 - PVA (architectural)









Ductal® Bridge Projects

	Canada	US
1997	1 st UHPC bridge in the world, pedestrian bridge, Quebec	
2005		1
2006	1 st joint fill project	
2007	3	
2008	2	2
2009	2	2
2010	5	
2011	7	5
2012	5	10
2013	12	26
2014	22	9
2015	24	14
total	84	69



Ductal® Bridge Projects

as of end 2015

States	# projects
New York	45
Pennsylvania	6
lowa	5
Massachusetts	2
Illinois	1
DC (Wash.)	1
Delaware	1
Montana	1
Nebraska	1
New Jersey	1
Ohio	1
Oregon	1
Virginia	1
Utah	1
Washington	1



Ductal® Bridge Projects

for 2016 working on over 30 projects

New States		
California		
Florida		
Georgia		
Hawaii		
Idaho		
Maine		
Minnesota		
South Carolina		
Vermont		





Joint fill applications – typical Ductal® formulations

JS1000

- 12 to 14 ksi in 4 days @ 70F
- Slow setting, can handle hot (90F) batching temperatures






JS1212

- 12 ksi in 12 hours @ 120F
- Fast setting to maintain workability, the batch temperatures are kept below 70F (use ice instead of water, if needed)






JS1000 – strength curves







JS1212 – strength curves







Field batching of UHPC

UHPC may be mixed in any type of mixer with proper mixer adjustments and optimization, but best performance is achieved in high shear mixers.

Most precast plant mixers work fine.



0.2 yd³ batches (0.8 yd³ per hour)



0.65 yd³ batches (2.6 yd³ per hour)



6 yd³ batches





$2/3 \text{ yd}^3$ – pan mixers




2/3 yd³ mixers – horizontal shaft






1.25 yd³ mixers – horizontal shaft








1.25 yd³ mixers – horizontal shaft







1.25 yd³ mixers – horizontal shaft







Quality Control on site

Slump Flow
Mini-slump cone
Flow - 7" to 10"





Compressive Strength
3" x 6" Cylinders
Ends cut to length & machined to <0.5°










Casting









Chillon Viaducs, Switzerland 2014-15

Use of portable plant on site



Hydro demolition



Material brought to the concrete machine with motorized buggies



On site portable batching plant – 2 mixers



Concrete paver with customized dispensing system at the front





Mission Bridge, British Colombia, Canada

Use of ready mix trucks to batch and deliver to site



Loading and batching in ready-mix truck at Lafarge plant



Delivery to the site (total of 4 trips)



Hoisting and casting from the top of the formwork



Completed project



Contact info

For more info on Ductal® applications, please contact:

Gaston Doiron, P.Eng., M.Eng.
 Project Manager, Repair & Retrofit Markets Ductal[®] cell: 416-579-7864
 gaston.doiron@lafargeholcim.com

www.ductal.com



